

FILTER CHECK







Operation Instructions

Warning! REMOVE Exhaust Plug and DO NOT obstruct airflow to the system!

- 1. Flip the Power Switch to the ON indication
- 2. Initialization is represented by a blinking **BLUE LED** (Allow up to 45 seconds)
- 3. A solid GREEN LED indicates the system is ready to begin filter testing if the following are verified:
 - i. Verify the flow rate to be 85 ± 1.19 SLPM (83.81 86.19 SLPM)
- ii. Verify the low-pressure sensor to be 0 ± 0.06 cmH2O
- 4. Placing a filter into the system will initiate testing to begin automatically
- 5. A blinking GREEN LED indicates the system is analyzing the inserted filter
- 6. A solid GREEN LED indicates the system has completed a test sequence of the inserted filter
- 7. DO NOT remove the filter until the pressure is recorded
 - i. Press the pause button on the display and record the pressure
- ii. Press the resume button and remove the inserted filter
- 8. Once the filter is removed, a BLUE LED will start blinking and the system will recalibrate
- *NOTE* To run another test, return to step 3

CBRNe Full Facepiece APR	Initial mmH2O	Initial cmH2O
Canister	50 ± 5.0	5.0 ± 0.50
Verification Orifice A	24 ± 2.4	2.4 ± 0.24

